United States Department of the Interior National Park Service

National Register of Historic Places Inventory—Nomination Form

For NPS use only received date entered

Continuation sheet

Item number 7 (and 8)

Page 15

NAME:

St. John the Baptist Catholic Church

LOCATION:

FM-Road 1383

Ammansville, Fayette County, Texas

OWNER:

Most Rev. Charles V. Grahmann, D. D.

Catholic Diocese of Victoria, Texas.

P. O. Box 4708

Victoria, Texas 77903

ARCHITECT:

John F. Bujnoch

BUILDER: John F. Bujnoch

INTERIOR CRAFTSMAN:

Unknown

SPECIFIC DATES:

1917 (construction)

GEOGRAPHICAL DATA:

Acreage of nominated property: less than one acre

UTM reference: 14/707020/3296900

Verbal boundary description: Beginning northwest of the church, at the intersection of the barbed wire fence with the road, proceed south along the road's edge to its intersection with the graveled parking area (approximately 174'), thence 90' east, along the edge of the parking area and in a direct line beyond, to a point along a line parallel with and 20' east of the church's easternmost wall, thence north along that line to its intersection with the barbed wire fence, thence west along the fence line back to the starting point (approximately 250').

DESCRIPTION:

St. John the Baptist Catholic Church, a 1918 statement in wood of the Gothic Revival style in rural Fayette county, stands out as the community's most significant building. The steeply gabled, rectangular form includes a polygonal apse projecting from its east end, and a soaring spire rising from a tall bell tower marking the central entrance at the west end. Prominent corner buttresses project from the front corners with lesser buttresses marking the remaining facades. Gabled and buttressed pavilions emphasize the

NPS Form 10-900-a (7-81)

United States Department of the InteriorNational Park Service

National Register of Historic Places Inventory—Nomination Form

received date entered

Continuation sheet

Item number

7 (and 8)

Page 16

OMB NO. 1024-0018

EXP. 10/31/84

For NPS use only

side entrances. The walls are pierced with lancet windows occurring both singly and in pairs. The Gothic theme is carried further by steeply pitched ventilation dormers with louvered trefoil openings and ridge ornaments. Corner buttresses adorn the bell tower, the upper section of which is punctuated with louvered lancet openings and a lancet jigsawn detail applied in a manner that emulates corbeling. The octagonal spire rises dramatically from a profusion of pinnacles and dormers incorporating trefoil motifs and cross-and-trefoil ornaments. Today the church is covered with asbestos siding. Yet the upper level of the bell tower reveals the original wood siding which is assumed to be intact under the asbestos.

While the exterior of St. John's is not unusual among the many Gothic Revival churches across the state, its distinct interior is outstanding for several reasons. Structurally the ceiling is composed of an unusual combination consisting of a high-pointed vault springing from two lesser, coved vaults. Aside from the unique structure of the ceiling, the church contains decorative painting which is more purely ornamental than any of the other churches in the thematic group. It incorporates stenciling, infill, freehand, and marbling techniques. The painting is executed with a simple color palette, and is dominated by one hue, a warm pink, which is offset by woodwork painted white. Rectangular panels defined with simple wooden dividers emphasize the ceiling's structural form, and the walls are divided into distinct horizontal sections. The rectangular panels of the ceiling are further defined by floral and foliate frameworks skillfully executed in varying shades of pink and bluegreen. Simple stenciled borders fill in the structural beams of the ceiling. The upper wall is decorated with a large-scale motif that includes circular and interwoven leaf elements set against a diagonal lattice. Garlands hang below this. Stylized floral motifs are stencilled onto the wall in two distinct bands at dado heights. As is typical, the apse spandrel and the walls of the side altar bear the religious motifs. Two small cherubs flank a chalice as the focal point of the spandrel, with palm fronds and blossoms (including lilies) painted around them. Palm fronds also occur on the walls above the side altars. The pilasters along the walls are painted to produce the appearance of marble.

SIGNIFICANCE:

A good example of early 20th-century Carpenter Gothic architecture, St. John the Baptist Catholic Church is an impressive visual monument to the Czech pioneers who settled in the area around Ammansville. The third church to occupy the site, it bespeaks the dedicated determination of these European immigrants. The handsome building is further distinguished with decorative interior painting, designed and executed by highly skilled artisans.

NPS Form 10-900-a

OMB NO. 1024-0018 EXP. 10/31/84

United States Department of the InteriorNational Park Service

National Register of Historic Places Inventory—Nomination Form

For NPS use only
received
date entered

Continuation sheet

Item number

7 (and 8)

Page 17

Andrew Ammann brought his family to the area in 1879, and was soon followed by other Czech settlers. The community, named Ammansville in his honor, was soon established as an agricultural center for the surrounding farmlands. These early settlers were primarily Catholic, and first attended mass at nearby Hostyn, and later at a local residence, before erecting their own church. A small, frame edifice was completed and dedicated in 1890 on land donated by three parishioners, but was destroyed by a hurricane in 1909. The congregation decided to reconstruct, and hired the Matuscik Brothers as architect and builder. This larger, more elaborate frame church, designed in the Gothic Revival style, was dedicated in November of 1910, only to be consumed by fire in 1917. Undaunted, the congregation chose to build a third church and engaged John Bujnoch as architect and builder. The church was dedicated on December 22, 1919, and stands today as a charming example of Carpenter Gothic architecture. Though simply detailed, the church rises above the surrounding countryside, and is an impressive architectural landmark in this rural region.

Interior painting, primarily decorative in intent, adorns the walls and ceiling of the church. The intricacy of design, sophisticated use of color, and skilled craftsmanship, indicate the work of professional artists. Warm pink is the dominant hue, and is used as a base color covered over with designs applied in varying values of pink and bluegreen. It is interesting to note that the motifs are chiefly ornamental in inspiration, drawing heavily on foliated and floral forms, with only occasional subtle ecclesiastical references occurring in the apse and in the areas of the side altars. Little is known of the history of the painting, although it is believed to have been executed soon after completion of the structure.

United States Department of the Interior National Park Service

National Register of Historic Places Inventory—Nomination Form

For NPS use only received date entered

Continuation sheet

Item number

Page 1 1 2

Multiple Resource Area Thematic Group dnr-11

Sta	ate Texas	_	- A	A
	mination/Type of Review			Date/Signature
1.	Ascension of Our Lord Catho Church	Intered in the National Registe		Aclores Byer 6/21/6
2.	Church of the Blessed Virgi the Queen of Peace	n Mary, Entered in the National Register		Selvus G/21/8
3.	Church of the Guardian Ange	National Register	Keeper	Selver Byer 6/21/8
			Attest	
4.	Church of the Immaculate Co of Blessed Virgin Mary	Entered in the National Register		Delous Byen 6/21/
5.	First Baptist Church	Entered in the National Register	Keeper	Selvus Byers 6/21
6.	First United Methodist Chur	d Methodist Church Substantive Review		Beth Grossena 6/3/83
			Attest	
7.		Entered in the	Keeper	Selvus Byen 6/21/8
		National Register	Attest	
8.		Entered in the		Deloua Byer 6/21/8
	N	ational Register	Attest	
9.	St. John the Baptist Cathol	ic Church Entered in the	Keeper	Delaus Byen 6/2/18
		National Register	Attest	
	St. Joseph's Catholic Churc	ch.	Keeper	DelousByen 6/21/8
wy	1 1 1 1 1 76	Entered in the National Register	Attest	

United States Department of the Interior National Park Service

> St. John the Baptist Catholic Church (Churches with Decorative Interior Painting TR) Fayette County TEXAS Working No. MAY 9 1083 Fed. Reg. Date: 2-7-84 Date Due: 6/9/83 -6/23/83 ACCEPT6/21/83 Action: resubmission ___ RETURN Entered in the National Register __ REJECT nomination by person or local government _ owner objection Federal Agency: _ appeal Substantive Review: __ sample ___ request ___ appeal ___ NR decision Reviewer's comments: Recom. / Criteria Reviewer_ Discipline Date___ see continuation sheet Nomination returned for: ____technical corrections cited below substantive reasons discussed below 1. Name 2. Location 3. Classification 4. Owner of Property 5. Location of Legal Description 6. Representation in Existing Surveys 7. Description s the present and original (If known) pi _ summary paragraph ___ completeness _ clarity alterations/integrity dates boundar selection

8. S	ignificance						
Poriod	Areas of Significance—C	Check and justify below					
Specific Statement	dates It of Significance (in one parag					Otalico ent Anatra vitoro: Vinus	St. Joan with Det Fuyette LEXAS
	completeness clarity applicable crite justification of checked	ria areas					
Marie Control	relating signification the resource context relationship of it to significations	integrity ince					
	justification of other	exception	,		4 - 5 - 10	amor Tel	about .
9. N	lajor Bibliograp	hical Reference	es				
Acreege of Guedrang UNIT Refe		A Part of the last		÷			
11.	Form Prepared	Ву		1			
The evalu	State Historic F sted significance of this property w netional state storic Preservation Officer signature deter	of thin the state is:	fficer Cer	tification			
13.	Other				A143 H 16		
	Maps Photographs Other						
Ques	tions concerning	this nomination	n may be	directed	to	Selection of the select	
Signe	od		Date			Phone: 202	272 - 3504



St. John the Baptist Catholic Church
Churches in Texas with Decorative
Interior Painting
Ammansville, Fayette County, Texas
Carol Kennedy
October, 1980
Texas Historical Commission, Austin, Texas
Exterior, Southwest oblique (camera facing
Northeast)

Photo #19 of 98



TEXAS HISTORICAL COMMISSION

St. John the Baptist Catholic Church
Churches in Texas with Decorative
Interior Painting
Ammansville, Fayette County, Texas
Carol Kennedy
October, 1980
Texas Historical Commission,
Austin, Texas
Interior, overall view toward altar

Photo #20 of 98



TEXAS HISTORICAL COMMISSION

St. John the Baptist Catholic Church
Churches in Texas with Decorative
Interior Painting
Ammansville, Fayette County, Texas
Carol Kennedy
October, 1980
Texas Historical Commission,
Austin, Texas
Interior, detail of wall and ceiling above side altar

Photo #21 of 98



TEXAS HISTORICAL COMMISSION

St. John the Baptist Catholic Church
Churches in Texas with Decorative
Interior Painting
Ammansville, Fayette County, Texas
Carol Kennedy
October, 1980
Texas Historical Commission,
Austin, Texas
Interior, detail of upper wall and
ceiling

Photo #22 of 98



TEXAS HISTORICAL COMMISSION

St. John the Baptist Catholic Church
Churches in Texas with Decorative
Interior Painting
Ammansville, Fayette County, Texas
Carol Kennedy
October, 1980
Texas Historical Commission,
Austin, Texas
Interior, detail of ceiling panels
over side aisles

Photo #23 of 98





St. John the Baptist Catholic Church
Churches in Texas with Decorative
Interior Painting
Ammansville, Fayette County, Texas
Carol Kennedy
October, 1980
Texas Historical Commission,
Austin, Texas
Interior, detail of wall dado

Photo #24 of 98

